4. Selections for prizes will be made by a committee of experienced and influential representatives of the raiyats that assemble at the place with the President of the Harihar Municipality as Chairman. Prizes will be distributed at the close of the show.

5. Every prize winner will receive a certificate in addition to his prize in money or of a medal.

6. In the absence of an eligible exhibit, the prize awardable thereto, will be withheld or awarded for any other exhibit of sufficient merit.

7. Intending exhibitors will apply to the Deputy Amildar of Harihar two days before the commencement of the show and get their names and description of their exhibit duly registered.

8. The owners of cattle for the show are expected to take due care of their animals and guard against accidents.

9. Owners will do well to make their own arrangements for providing their cattle with fodder as the local supply which will be made available at reasonable rates, may not suffice to meet the requirements of more than a limited number of cattle adjudged suitable for the show.

10. The jatra is generally well attended and will afford a good market for dealers in cattle, etc.

11. Arrangements will be made to exhibit and work improved ploughs.

T. G. RAMA IYER,
For *Deputy Commissioner.*

MYSORE DIVISION.

Dated 14th February 1911.

Notice is hereby given that a sum of Rs. 29-13-4 has been outstanding in favor of contractor Mallish, in the accounts of this office from the year 1896. If the amount is not claimed within three months from this date, the same will be credited to Government.

R. V. SUNDARAM IYER,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 15th February 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 15th March 1911, for improving the Nirgunda tank R. No. 114, Hosdurga Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving the Nirgunda tank or No. 114, Hosdurga Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Improving Nirgunda tank, Registered No. 114, Hosdurga Taluk.

No.	Details of work	Per	Quantity
	Bund R. L. 57·00, Revetment 55·00, top 6'—		
1	Earthwork, including watering and tamping, etc. ..	C. yd.	15,555
2	Gravel backing	"	1,760
3	Turfing	S. yd.	18,850
4	New stone revetment	C yd.	1,255
5	Old do with new jelly	"	849
6	Grade stones with bed slabs	Each	4
7	Top width or index stones	"	4
8	B. M stones	"	2
9	Register No. stones	"	1
10	Date stones	"	1
11	Gauge stones with bed slab	"	2
	Sluices.		
12	Sluice No. 1, repairing the front and rear cisterns preparing a new plug, etc.	L. S.	L. S.
13	Sluice No. 2, repairing the cisterns, vents, stopping leakages, etc.	"	"
14	Sluice No. 3, blocking up the sluice	"	"
	Waste weirs.		
	Left weir, 240 feet long, R. L. 50·00—		
15	Earthwork	C. yd.	353
16	Burnt brick in surki mortar	C. ft.	1,453
17	Plastering with surki mortar	Sqr.	14·08
18	Burnt stone slabs	S. ft.	487
19	Sujjout apron	L. S.	L. S.
	Right waste weir, 126 feet long, R. L. 50·00—		
20	Earthwork	C. yd.	28
21	Burnt brick in surki mortar	C. ft.	1,201
22	Plastering in surki mortar	Sqr.	9·82
23	Burnt stone slabs	S. ft.	452
24	Sujjout apron	L. S.	L. S.
	Miscellaneous.		
	Protection bund—		
25	Earthwork	C. yd.	1,451
26	New stone work	"	85
27	Turfing	Sqr.	472
28	Making steps in the bund near village site for the convenience of the people to carry water, etc.	L. S.	L. S.

C. KRISHNAIENGAR,
Executive Engineer.